**DOCUMENT CONTROL**

- **Title:** ANNEX E: VENDOR SERVICE LEVEL AGREEMENT (SLA) BASELINES
- **Parent Document:** Hawassa City MESOB Master Blueprint
- **Target Audience:** Technical Steering Committee, Legal Department, Vendor Account Managers
- **Status:** Requirements Definition for Contract Negotiation

---

# ANNEX E: VENDOR SERVICE LEVEL AGREEMENT (SLA) BASELINES

## 1. PURPOSE AND SCOPE

This document defines the **Minimum Performance Standards** required for the operation of the Hawassa City MESOB One-Stop Service Center. It serves as the technical schedule to be attached to the Master Services Agreements (MSAs) with strategic partners (primarily Ethio Telecom and the Federal Artificial Intelligence Institute - EAII).

**Strategic Intent:**
To translate the "Governance Transformation" mandate into enforceable technical metrics. These baselines are designed to prevent "Vendor Lock-in" where the City pays for services that are functionally unusable due to latency, downtime, or poor support.

**Scope of Application:**

1. **Infrastructure & Connectivity:** (Provider: Ethio Telecom)
2. **Software & Application Stack:** (Provider: EAII)
3. **Local Support & Maintenance:** (Provider: Local IT Contractors)

---

## 2. CRITICALITY DEFINITIONS & SEVERITY LEVELS

To avoid ambiguity during a crisis, all technical incidents must be categorized according to the following severity matrix.

| Severity Level | Definition | Example Scenarios |
|---|---|---|
| **P1: CRITICAL (Emergency)** | **Complete Service Stoppage.** The MESOB Center cannot process citizens. Data integrity is at risk, or the primary link to | • Fiber cut (Primary & Backup down).<br>• API Gateway failure (0 transactions possible).<br>• Payment Aggregator failure (Telebirr/CBE |

| | | |
|---|---|---|
| | the Federal Cloud is severed with no backup. | down).<br>• Security breach (Ransomware/Data theft). |
| **P2: HIGH (Major)** | **Severe Performance Degradation.** The center is open, but processing speed is crippled, or a critical module is offline. Workarounds are difficult. | • Latency > 200ms making the system unusable.<br>• One specific bureau module (e.g., Trade) is offline.<br>• Queue Management System (QMS) failure.<br>• Local Edge Server synchronization failure. |
| **P3: MEDIUM (Minor)** | **Partial Functional Limitation.** Specific features are broken, but the core workflow continues. Workarounds exist. | • SMS Notifications not sending.<br>• Reporting Dashboard lag.<br>• Printer network issues in one zone.<br>• Single workstation failure. |
| **P4: LOW (Cosmetic)** | **Non-Critical Issue.** Inconvenience that does not impact service delivery. | • Typos in the portal UI.<br>• Minor glitches in the admin panel.<br>• Feature request or inquiry. |

---

# 3. INFRASTRUCTURE SLA (Target: Ethio Telecom)

This section governs the physical and logical connection between the Hawassa MESOB Local Edge Data Center and the National Digital Backbone.

## 3.1 Availability (Uptime)

- **Requirement:** The Wide Area Network (WAN) and Cloud Services must meet a **99.9% Availability** target during business hours (08:00 – 20:00, Mon-Sat).
- **Measurement:** Calculated monthly.
  - *99.9% = Max 43 minutes of unplanned downtime per month.*
- **Redundancy Clause:** The SLA applies to the *service*, not just the fiber cable. If the Primary Fiber is cut but the Microwave Backup kicks in automatically within 60 seconds, the service is considered "Available."

## 3.2 Network Performance Metrics

The "Nine Systems" rely on rapid database queries. Slow internet is equivalent to no internet.

| Metric | Baseline Target | Measurement Method |
|---|---|---|
| **Latency (Round Trip Time)** | **< 40ms** (Hawassa Edge ↔\leftrightarrow↔ Federal Cloud) | Ping tests every 5 minutes. Average over 24 hours. |
| **Packet Loss** | **< 0.1%** | End-to-end active monitoring. |
| **Throughput (Bandwidth)** | **100% of Committed Information Rate (CIR)** | If City pays for 500Mbps, speed tests must show >490Mbps consistently. |
| **Jitter** | **< 10ms** | Critical for video conferencing (Mayoral Court). |

### 3.3 Incident Response Times (Infrastructure)

| Severity | Response Time (Acknowledgment) | Resolution Target (Fix Time) | Updates Frequency |
|---|---|---|---|
| **P1** | 15 Minutes | 2 Hours | Every 30 Minutes |
| **P2** | 30 Minutes | 4 Hours | Every 1 Hour |
| **P3** | 2 Hours | 8 Hours (1 Business Day) | End of Day |
| **P4** | 24 Hours | 48 Hours | Upon resolution |

---

# 4. SOFTWARE & APPLICATION SLA (Target: EAII)

This section governs the performance of the "Nine Systems" (Identity, Workflow, Payment, etc.) running on the Local Edge and Cloud environments.

### 4.1 Application Performance

- **Page Load Time:** The e-Service Portal must load in **< 2 seconds** for 95% of requests.
- **API Response Time:** Internal API calls (e.g., Workflow Engine querying the Database) must complete in **< 500ms**.
- **Transaction Finality:** A payment confirmation (from Telebirr API to MESOB Receipt generation) must complete in **< 5 seconds**.

### 4.2 Integration & Interoperability

- **Fayda Authentication:** The system must validate a National ID biometric scan in **< 3 seconds**.
- **Data Synchronization:** Transactions recorded on the Local Edge Server must sync to the Federal Cloud within **15 minutes** of restoration after a connectivity outage.

### 4.3 Bug Fix Guarantee

- **Critical Bugs (Data Loss/Security Risk):** Patch must be deployed within **12 hours**.
- **Functional Bugs (Broken workflow step):** Patch must be deployed within **3 business days**.

---

# 5. MAINTENANCE & CHANGE MANAGEMENT POLICY

To prevent "Surprise Downtime," vendors must adhere to the following maintenance window protocols:

1. **Standard Maintenance Window:** All non-emergency updates must occur between **22:00 – 05:00**.
2. **Notification Period:**
    - Planned Maintenance: Minimum **72 hours notice** to the City IT Lead.
    - Emergency Patching: Minimum **30 minutes notice** (with justification).
3. **No-Change Fridays:** No major updates shall be deployed on Fridays to prevent weekend outages when support staff are reduced.

---

# 6. PENALTIES, CREDITS & ESCALATION PROTOCOLS

Recognizing the difficulty of imposing cash fines on federal entities, Hawassa City adopts a **Service Credit** and **Political Escalation** model.

## 6.1 Service Credits (Financial Remedy)

Instead of paying a fine, the Vendor deducts value from the *next* month's bill based on downtime.

| Monthly Availability | Service Credit (Deduction from Monthly Fee) |
|---|---|
| 99.9% - 100% | 0% |
| 99.0% - 99.8% | 5% |
| 98.0% - 98.9% | 10% |
| 95.0% - 97.9% | 25% |
| Below 95% | 50% + Right to Contract Review |

## 6.2 The Federal Escalation Trigger (Political Remedy)

If a vendor fails to meet P1/P2 resolution times three times in a single quarter, the Hawassa City Administration invokes the **"Federal Alignment Protocol"**:

1. **Level 1 (Operational):** Formal warning letter from City MESOB Director to Vendor Regional Head.
2. **Level 2 (Executive):** Direct call from Hawassa Mayor to Vendor CEO.
3. **Level 3 (Regulatory):** Formal incident report filed with the **Ministry of Innovation & Technology (MInT)** and the **Digital Transformation Council**, citing non-compliance with the National Digital Strategy.

---

# 7. REPORTING & GOVERNANCE

The Vendor is required to provide automated, transparent reporting. "Trust us, it's working" is not acceptable.

1. **Real-Time Dashboard:** The City IT Team must have "Read-Only" access to the Vendor's monitoring tools (e.g., NMS, APM) to verify uptime independently.
2. **Monthly Performance Report:** Submitted by the 5th of every month, detailing:
    - Actual Uptime vs. Target.
    - List of all P1/P2 incidents and Root Cause Analysis (RCA).
    - Bandwidth utilization graphs.
    - Security attempted intrusions and blocks.

---

**APPROVAL**

This Annex constitutes the technical baseline for negotiation. Any deviation requested by a Vendor must be formally documented as a "Risk Acceptance" and signed by the Steering Committee.

**End of Annex E**